BRUHAT BANGALORE MAHANAGARA PALIKE

MODIFIED APPROVED SCHEDULE - B

Name of the work: Modified Estimate for Improvements to Roads and Drains at BEL 2nd Block in Ward No. 10,(Doddabommasandra) Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Quotation Rates of K. Anil Kumar	
				In Figures	In Words
1	270.90	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications	cum	75	Rupees Seventy Five Only
2	305.44	Providing, laying, spreading and compacting graded stone aggregate to **wet mix macadam** specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications qty upto 125%	cum	1000	Rupees One Thousand Only
3	1024.69	Qty Above 125%	cum	1553.88	Rupees One Thousand Five Hundred Fifty Three
3	6406.70	Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WBM, WMM including cleaning of road surface and spraying primer at the rate of 0.60 Kg / sqm using mechnical means complete as per specifications. MORTH specification	sqm	31	Rupees Thirty One Only
4	103.36	KSRRB M500-18: Providing and laying **semi dense bituminous concrete** using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 500.8 complete in all respects as per specifications. **with 100-120 TPH capacityH.M.P with sensor paver Gr-II (25 mm to 30 mm) with 5 % VG-30 Bitumen**	cum	8000	Rupees Eight Thousand Only
5	135.45	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km	cum	73	Rupees Seventy Three Only

Anilkumar K.

E.E. (BTP. DIV)

Sr. No.	Approved Qty.	Description	Unit	Approved Quotation Rates of K. Anil Kumar	
				In Figures	In Words
6	90.90	KSRRB M500-19: providing and laying **bituminous concrete** 40mm thick with hot mix plant, using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desire compaction as per MORTH specification clause No. 500.9 complete In all respects as per specifications. MORTH specification NO. 509, **using 40/60 TPH capacity H.M.P with Mechanical paver Gr-II (30 to 45 mm) with 6% VG-30 Bitumen,**	cum	6980.20	Rupees Six Thousand Nine Hundred Eighty and Twenty Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92